

GATX



GENERAL AMERICAN TRANSPORTATION CORPORATION

AD655904

AD655904

SHEMER LIGHTING KIT

by

R. B. Neveril

H. P. Behis

CCD Work Unit 1487A

Final Report 1-67

January 1967

Distribution of this document is unlimited.

RECEIVED

AUG 11 1967

CFSTI

GENERAL AMERICAN RESEARCH DIVISION

7446 NORTH NATCHEZ AVENUE, NILES, ILLINOIS 60648 312/847-9000

67

Prepared for
Office of Civil Defense
Department of the Army, OSA
under
Work Unit 1427A
SRI Subcontract No. B87001(4949A-62)-US

SHELTER LIGHTING KIT

by

R. B. Neveril

H. F. Behls

OCD Work Unit 1427A

ARD Report 1400

January 1967

Distribution of this document is unlimited.

Reviewed by:

G. Engholm

G. Engholm
Group Leader
Environmental Research


Approved by:

P. Rosenberg

P. Rosenberg
General Manager

REVIEW NOTICE

This report has been reviewed in the Office of Civil Defense and approved for publication. Approval does not signify that the contents necessarily reflect the views and policies of the Office of Civil Defense.



**Best
Available
Copy**

FOREWORD

The General American Research Division (GARD) of General American Transportation Corporation was contracted by Stanford Research Institute (SRI) for the Office of Civil Defense to design a prototype Lighting Kit for use in fallout shelters. This program was performed under SRI Subcontract B-87001(4949A-62)-US, OCD Work Unit 1427A, with Mr. James F. Halsey of SRI serving as project monitor.

GENERAL AMERICAN RESEARCH DIVISION

ABSTRACT

The Shelter Lighting Kit includes a manually-driven power unit and a fluorescent lighting system. Two power unit designs are presented for preproduction fabrication and evaluation. One power unit has a generator mounted on a bicycle-type frame and driven by a chain and sprocket transmission; while the other unit has a generator with an integral geared transmission mounted on a folding tripod frame. Both power units are designed for one-man operation with a power input of 0.1 horsepower at a nominal pedal speed of 55 rpm and a nominal generator output of 50 watts at 120 volts AC. The selection of either design for the production model will depend on their performance and a cost analysis. The fluorescent lighting system consists of two adjustable lamp fixtures and two 20-watt or 25-watt preheat fluorescent lamps operated in series (selected lamp wattage will depend on the overall system efficiency). The estimated production cost of the lighting kit is \$90.

An incandescent lighting system is proposed as an optional accessory for night lighting or background illumination in multi-room shelters. This lighting system consists of five 10-watt incandescent lamps with adapter sockets and five 50-foot extension cords. The estimated cost of this accessory is \$7.30.

TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE</u>
	FOREWORD	iii
	ABSTRACT	v
1	INTRODUCTION	1
2	DESIGN CRITERIA AND EVALUATION	3
	2.1 Lighting	3
	2.1.1 Fluorescent	3
	2.1.2 Incandescent	6
	2.1.3 Lighting Analysis	6
	2.2 Generators	10
	2.2.1 AC Alternators	10
	2.2.2 DC Generators	11
	2.2.3 Generator Analysis	12
	2.3 Experimental Evaluation	15
	2.3.1 Description of Experimental Unit	15
	2.3.2 Lighting	18
	2.3.3 Voltage Regulation	20
3	DESIGN	21
	3.1 Basic Lighting Kit	21
	3.1.1 Power Unit	21
	3.1.1.1 Roller Chain Transmission Design	21
	3.1.1.2 Integral Transmission Design	24

GENERAL AMERICAN RESEARCH DIVISION

TABLE OF CONTENTS (CONT'D)

<u>SECTION</u>		<u>PAGE</u>
	3.1.2 Fluorescent Lighting System	26
	3.1.3 Cost Analysis	28
	3.2 Accessory Incandescent Lighting System	28
	REFERENCES	33
APPENDIX A	Drawings - Power Unit With an External Roller Chain Transmission	
APPENDIX B	Drawings - Power Unit With an Integral Geared Transmission	

SECTION 1

INTRODUCTION

According to the Second National Fallout Shelter Survey there are 226,000 basement and special facilities (such as mines, caves, etc.) which can accommodate 55.8 million people. These facilities generally have no natural illumination and therefore require a means of artificial lighting. Approximately one-quarter to one foot candles of illumination are needed in these shelters to maintain the minimum survival requirements (Ref. 1). In addition to this background illumination, higher levels are required in the administrative, medical, and kitchen areas.

The emergency lighting systems considered to date for these shelters are:

- 1) a 100-watt "Light Admitting Device" which uses the sun as a light source and a mirror system for distribution (Ref. 2),
- 2) a 550-watt "Self-Contained Generator" which produces electrical power and provides oxygen and water through the decomposition of 90 percent hydrogen peroxide (Ref. 3),
- 3) a series of 0.5 to 5 KVA generators driven by four-cycle engines using liquified-petroleum gases (propane and butane) as the fuel (Ref. 4), and
- 4) an automotive generator driven either manually or by a gasoline engine (Ref. 5).

These systems are either expensive, require periodic maintenance, or are difficult to operate manually. Item 4 above consisted of both an automotive alternator and an automotive generator driven independently through a 24-inch bicycle. In this case, two methods of coupling were attempted: direct friction

drive, which proved too difficult to operate, and belt drive. Pedaling the alternator at 60 rpm through a belt drive transmission resulted in 36 watts of power and could be sustained for a maximum of five minutes. It was also found that charging of a storage battery with this system was not practical. The maximum charge obtained was 2 amps for one minute with physical endurance being the limiting factor. These alternators and generators are specifically designed for larger loads and high speeds with power inputs of up to 4 horsepower. Since these generators are not designed for manual operation, the Office of Civil Defense initiated this program to study the design and development possibilities of an inexpensive lighting kit consisting of a fluorescent or incandescent lighting system and a power unit which can be manually driven by one person for extended periods of time. The primary function of the lighting kit is to furnish illumination with emphasis on maximum efficiency and performance at minimum costs. A secondary function of the power unit could be to furnish a means of recharging dry cell batteries, which are used in Civil Defense radiological equipment, or operating radio receivers in the shelters.

GENERAL AMERICAN RESEARCH DIVISION

SECTION 2

DESIGN CRITERIA AND EVALUATION

The basic considerations in designing a shelter lighting kit are human factors, types of lighting, and methods of generating electrical power. An extensive amount of data concerning human factors (such as pedal speeds, optimum and maximum power inputs, and work/rest cycles) has been established in the development of the shelter Ventilation Kit as described in Specification MIL-V-40645 (Ref. 6); however, little data has been documented on the optimum types of lighting and the methods of electrical power generation for this application. This section analyzes types of lighting systems and generators for use in a shelter lighting kit, and evaluates them by means of an experimental unit. Section 3 presents the design of a matched lighting and generator system.

2.1 Lighting

The two types of artificial illumination suitable for a shelter application are fluorescent and incandescent lighting. The type selected depends on its application (high intensity or background illumination), the lumen output, the total cost of the lighting system, and the performance characteristics of the power source.

2.1.1 Fluorescent

The fluorescent lamp is an electric discharge lamp usually in the form of a long tube coated internally with one or more fluorescent powders commonly called phosphors. Cathodes are located at each end of the tube. The lamp is filled to a low pressure with a noble gas to which usually is added a small drop of mercury. The discharge passing through this gas and mercury vapor generates ultraviolet radiation which in turn excites the phosphor to emit light.

Since fluorescent lamps have a negative resistance characteristic, they must be operated in circuits which include current control, such as a ballast, in series with the lamp. A number of different means of lamp starting have been developed since the advent of the fluorescent lamp (Ref. 7). The first is preheat-starting using low voltage but requiring an automatic or manual starting switch. In this method of starting, a circuit which connects both cathodes of the lamp in series with the power source is closed by an automatic or manual switch. The cathodes are momentarily heated (approximately 1 second) and the immediate surrounding gas is ionized. The cathode circuit is then opened by the switch, causing a transient voltage to be built up in the ballast. This voltage is sufficient to strike the arc between the cathodes and start the lamp. Once the lamp starts, the ballast acts as a current limiting device, since there is essentially a short circuit across the lamp. The second method is instant-starting, which requires a higher voltage, but no cathode heating. The ballast, functioning as a transformer, impresses a high voltage (400 to 1000 volts) across the cathodes of the lamp to strike the arc. The most recent method is rapid-starting, where the use of continuously heated cathodes has resulted in lamp starting without high voltage or starting switches.

Fluorescent lamps designed for preheat and rapid starting are the most commonly used lamps in sizes 40-watt and less. Instant-start lamps are generally used in larger sizes and require more input power. Table I shows costs and performance data for typical and commercially available preheat and rapid-start fluorescent lamps.

TABLE I

PERFORMANCE OF FLUORESCENT LAMPS

TYPE OF LAMP	PREHEAT												RAPID START
	4	6	8	13	14	15	20	25	30	40			
Nominal Rating, Watts	4									40			30
Actual Power Input, Watts	3.7	5.8	7.9	13.0	13.4	15.0	19.6	26.0	30.4	40.0			30.0
Lamp Operating Volts	32	45	56	96	37	55	55	60	98	101			75
Light Output, Lumens (see Note 2)	113	250	400	735	720	850	1250	1815	2180	3250			2400
Ballast Power Loss, Watts	2	2	2	6	6	5	6	6	11	11			14-20
Lamp Cost, dollars	0.80	0.80	0.80	0.92	0.56	0.56	0.51	1.08	0.66	0.58			0.80
Starter Cost, dollars	0.22	0.22	0.22	0.12	0.12	0.12	0.12	0.20	0.12	0.12			0.00
Ballast Cost, dollars	0.42	0.42	0.42	1.77	3.47	3.47	3.47	0.64	3.47	3.47			3.87
Lumens Per Lamp Watt	30	43	50	56	53	56	64	70	71	81			80
Lumens Per Lamp-Starter Dollar	111	245	392	706	1075	1250	1985	1445	2880	4640			3000
Lumens Per Lamp-Starter-Ballast Dollar	78	173	278	262	173	205	305	946	513	780			515

NOTES: (1) Based on quantity of 100,000 units (Ref. 8).

(2) White and warm white lamps.

(3) Ballast with low power factor.

2.1.2 Incandescent

Incandescent lamps are available in a variety of bulb shapes, sizes, bases, filaments, and colors (Ref. 9). Each lamp is designed for a particular application, such as general illumination, infrared heating, floodlighting, and spotlighting. Lamp operating voltages range from 6 volts to 260 volts, alternating current or direct current, and the lamps are rated from 3 watts to 1,500 watts. Table II presents the performance data and costs for typical incandescent lamps with medium bases (screw-type, 120 volt).

Table II

PERFORMANCE OF INCANDESCENT LAMPS

Nominal Lamp Watts	7.5	10	15	25	40	50
Lamp Operating Volts	115-125	115-125	120	120	120	120
Light Output, Lumens	53	79	144	262	470	685
Lamp Cost, Dollars	0.11	0.11	0.11	0.12	0.12	0.12
Lumens Per Lamp Watt	7.1	7.9	9.6	10.5	11.7	13.7
Lumens Per Lamp Dollar	482	718	1310	2180	3920	5700

NOTES: 1) Based on General Electric Company data (Ref. 10).
2) Based on quantity of 100,000 units (Ref. 11)

2.1.3 Lighting Analysis

The significant advantage of fluorescent lighting is that it produces a lumen output approximately six times that of incandescent lighting for the same power input (see Tables I and II); however, using fluorescent lights in a shelter lighting kit has a few disadvantages, such as its greater cost, the power losses in the accessories, and the length of the lamps. The cost of the ballast and starter required in the standard fluorescent lighting

circuit can be as much as seven times the cost of the lamp. For example, a 20-watt fluorescent lamp costs \$0.51, while the ballast costs \$3.47. The power consumed by the ballast is high and can be as much as one-third that consumed by the lamp. A 20-watt fluorescent lamp has an additional 6-watt loss in the ballast. Fluorescent lamps can present a safety hazard if the tubes are broken because they contain mercury vapor. This gas is noxious and if allowed to escape from a broken lamp could present a health hazard in a small closed room. Generally, shelters are large and are ventilated sufficiently so that this problem is not significant.

The advantages of incandescent lighting are its greater simplicity, lower cost, and compactness. Although the light output of an incandescent lamp is approximately one-sixth that of a fluorescent lamp, the cost of an incandescent lamp is approximately one-thirtieth. For example, the cost of a 40-watt fluorescent lamp with accessories (excluding the fixture) is \$4.17, whereas, the cost of a 40-watt incandescent lamp is only \$0.12. This large cost difference is primarily due to the cost of the ballast in the standard fluorescent lighting circuit. When comparing the light output of fluorescent and incandescent lamps on a cost basis, it can be seen that a standard fluorescent light circuit is extremely expensive (see Tables I and II). If the ballast could be deleted for a shelter lighting system, this method of illumination would be more economical. For example, the comparison of a 40-watt system is shown in Table III.

TABLE III
COMPARISON OF 40-WATT FLUORESCENT AND INCANDESCENT
LIGHTING SYSTEMS

SYSTEM*	COST	LUMENS PER DOLLAR
Standard circuit with Lamp, Starter, and Ballast	\$ 4.17	780
Special circuit with Lamp and Starter. No Ballast.	0.70	4640
Incandescent Lamp.	0.12	3920

*Fixture costs are not included.

It is possible to eliminate the ballast in a fluorescent lamp circuit (see Section 2.3.2) by selecting a generator which has an impedance that is matched to the characteristics of the lamp. If preheat fluorescent lamps are used, the windings of the generator can produce the transient voltage or inductive "kick" required to strike the arc when the switch in the cathode circuit is opened. The impedance of the windings will limit the current once the lamp has started. With this arrangement, the lamp ballast is essentially built into the generator and the high cost and power losses normally associated with a standard ballast are eliminated. Fluorescent lighting using the generator to provide the ballast for the lamp is ideally suited for the shelter lighting kit.

The selection of the optimum number and size of lamps to be included in a lighting kit depends on the efficiency of the power unit and the available input horsepower. Table IV shows the estimated power for a nominal 0.1

horsepower unit using incandescent and fluorescent lamps. The 40-watt fluorescent lamp has the highest lumen per watt rating (81 lumens per watt) of all the individual lamps (see Table I); however, a lighting system using a single lamp has an undesirable effect of concentrating all the light in one location. Two 20 or 25-watt fluorescent lamps can be placed in series to provide a more even distribution of light over a larger area and in more than one room. In addition, these lamps can be readily packaged within the kit, while the 40-watt lamp (48 inches long) would require an unreasonable packaging problem. Two 25-watt lamps in series can be used with power units that have gear transmissions with mechanical efficiencies of 90 percent or higher. Two 20-watt lamps in series would be used with power units having lower efficiencies (see Section 2.2.3). Of primary importance is the reduced light output when using either five 10-watt or one 40-watt incandescent lamp. Any of these arrangements will result in a power input to the system less than 0.127 horsepower.

TABLE IV
POWER REQUIREMENTS FOR FLUORESCENT LIGHTING

LAMPS				Length (inches)	Operating Volts	Light Output (lumens)	Generator Input Watts ¹	Manual Horsepower Input	
NO.	WATTS		Chain Drive ² 80% Efficiency					Gear Drive ³ 90% Efficiency	
	Nominal	Actual							
Fluorescent	2	15	30.0	18	110	1700	44.1	0.074	0.066
	2	20	39.2	24	110	2900	56.2	0.094	0.084
	2	25	52.0	33	120	3630	75.5	0.127	0.113
	1	40	40.0	48	101	3250	57.3	0.096	0.085
Incandescent	5	10	50.0	---	115-125	395	72.2	0.121	0.107
	1	40	40.0	---	120	470	57.3	0.096	0.085

NOTES:

1. Generator efficiency based on performance data as shown in Figure 2.
2. See Section 2.2.3 for the estimated efficiency for the chain transmission.
3. See Section 2.2.3 for the estimated efficiency for the gear transmission.

2.2 Generators

The selection of a generator for a manually-driven power unit depends upon its simplicity, compactness, performance characteristics (such as its efficiency and speed at which it must be driven), control, and cost. The two basic types of generators are alternating current (AC) alternators and direct current (DC) generators.

2.2.1 AC Alternators

Alternators generally have the armature as the stator or stationary member, and the field as the rotating member. These alternators are categorized according to the method of field excitation; such as (1) externally excited, (2) self-excited, and (3) permanently excited.

The externally excited alternator is generally designed for power plants. The excitation current, which is low voltage DC, is carried through slip rings which are easily insulated at these voltages. The power required to excite the field windings is less than 1-1/2 percent of the rated power of the machine. The simplest manner of achieving control is through a rheostat in the field circuit. The rheostat controls the field current, and thus the magnetic flux-density.

The self-excited generator is designed for the intermediate power range, the smallest being rated at approximately 200 watts. This machine uses a portion of the output voltage, which is carried through slip rings, although residual magnetism in the field is required to initially induce a voltage in the armature at start-up.

The permanently excited alternator has magnets in the field which produce a magnetic field of constant strength. These alternators are normally designed for the low power output range (up to 250 watts) and have linear speed-voltage

characteristics. Since the field is permanently excited, these machines have no slip rings and the output voltage is solely dependent on the speed at which the alternator is driven. There are two types of permanently excited alternators. One type has a rotor containing permanent magnets with the armature windings located in the stator; while the second type, called a flux switch alternator, has both the permanent magnets and the armature windings located in the stator. The rotor in this case merely provides the magnetic flux path between the positive and negative poles of the magnets. This flux path also passes through the armature windings. As the angular position of the rotor is changed, the flux alternately passes through the rotor from one set of poles to the next set of poles. As the flux alternates between the magnetic poles of the stator, a reversal of the direction of the flux through the armature windings occurs, thereby inducing a voltage in these windings. The flux switch alternator is primarily designed for high speed, high frequency applications, and is most efficient under these conditions.

2.2.2 DC Generators

The construction of the DC generator is somewhat different than the AC alternator. In this case, the armature is the rotating member and the field is located in the stator or stationary member. The DC generator, however, operates in the same manner as the AC alternator; i.e., a voltage is generated in the armature windings with an alternating waveform. The distinct difference in the two machines is in the delivery of the voltage to the load. In the AC machine, the waveform appearing at the load is the same as that in the winding, but in the DC machine, one-half of the wave is reversed by the commutator. With sufficient coils spaced around the armature, the ripple in the voltage is reduced to an insignificant quantity in the practical machine. There are

three standard types of DC generators: the shunt generator, the series generator, and the compound generator.

The field of the shunt generator in series with its rheostat is connected directly across the armature. The rheostat, or voltage regulator, controls the strength of the field in order to regulate the output terminal voltage. Shunt generators are commonly used in city power substations. This type of generator, in addition to an AC alternator with a built-in rectifier, also has wide application in the automotive and truck industry and is designed for 6, 12, and 32 volt systems.

In the series generator, the entire load flows through the field winding, which consists of relatively few turns of wire of sufficient size to carry the entire load current without undue heating. This generator supplies constant current, and has been used to operate series arc lamps.

By addition of a series winding to the shunt generator, a constant terminal voltage may be automatically maintained. This generator is known as a compound-wound generator and is chiefly used to supply a pure motor load subject to rapid fluctuations, such as in railway work.

2.2.3 Generator Analysis

The permanently excited alternator is best suited for the power unit of a shelter lighting kit since this machine is inexpensive, compact, requires the least maintenance, and can be used on fluorescent lighting systems. The impedance of the armature windings can be designed to provide both the necessary cathode heating amperage for starting fluorescent lamps, and the required operating amperage after starting, without changing the speed of the alternator. This alternator can also be short-circuited repeatedly without damage to the armature windings.

The permanent magnet rotor alternator is best for a manually-powered application. This type of alternator is designed for slower speeds; whereas the flux switch alternator is designed for high speeds (2,000 to 100,000 rpm), and requires complex transmissions and speed increasers. The optimum trade-off speed for a permanent magnet rotor alternator and its transmission is approximately 1800 to 2100 rpm. Higher speeds reduce the cost of the alternator, but increase the transmission costs. Slower speeds result in a larger, more expensive and less efficient alternator. Considering a pedal speed of 55 rpm, an alternator speed of 2,000 rpm would require a transmission speed ratio of 36.4 to 1.

The four basic types of transmissions that can achieve this 36.4 to 1 speed ratio are belt-drives, friction drives, chain drives, and gear drives. The belt and friction drives are too inefficient for a manually-driven application with low power inputs (Ref. 12); therefore, the transmission is limited to either gear or chain drives. The efficiency of a 36.4 to 1 chain transmission driven at 2,000 rpm is approximately 80 percent (Ref. 13); while the efficiency of a similar gear transmission is estimated to be at least 90 percent. The overall efficiency of the alternator and transmission must be determined by test. After prototypes have been built, the transmission should be selected based on cost and the overall size and volume of the lighting kit package.

Although the shunt-wound DC generator, which is mass-produced for vehicle manufacturers, costs less than a permanent magnet generator produced in small quantities, the disadvantages of using this type of generator in a lighting kit are: 1) the lighting system would be limited to incandescent lamps which produce

approximately one-sixth the light output of fluorescent lamps, 2) larger capacity wiring looms would be required to carry the high currents of a low voltage system, 3) the transmission would be more expensive since these generators are designed to operate at speeds from 2,000 to 10,000 rpm, and 4) the power losses in the generator windings and the voltage regulator are comparatively high due to the large currents. It is possible to operate fluorescent lamps from a DC circuit; however, a polarity reversing switch, a special ballast, a resistor, and a transformer are required. These accessories would consume a substantial amount of power. For instance, a 40-watt lamp would have an additional 44 watt power loss in the accessories for a total required power input of 84 watts.

The single advantage of a low voltage DC system is that electrical energy can be stored in a battery so that power is available at all times. The significance of this method is that lighting can be provided at night and other times when it is not desirable to operate the generator. The disadvantages of interposing a lead-acid battery between a DC generator and the load, or a battery and battery charger between an AC generator and the load, are as follows:

- (1) The efficiency of either system is reduced since the watt-hour efficiency of lead-acid batteries is approximately 77 percent. Normally, the rated discharge for a battery is based on eight hours; therefore, a 40 ampere-hour battery (typical 12 volt automobile battery) would deliver approximately 60 watts for 8 hours until completely discharged and require a recharge rate of 71 watts for 8.8 hours. Increased discharge rates would

reduce the ampere-hour rating and the watt-hour efficiency of the battery.

The use of a battery charger in conjunction with a 120 volt AC generator will further reduce the system efficiency. Battery chargers have an efficiency of 65 to 75 percent; thus, producing an overall efficiency for the battery/battery charger combination of 50 to 55 percent.

- (2) As stated previously, the typical automobile generator is not practical for a manually-powered application, since it is designed for large power outputs at high speed and is relatively inefficient, particularly with light loads or low speed. For example, the Leece-Neville type A001-6000 generator has an output of 54 watts at 1000 rpm with an input of 0.37 horsepower. The generator for a manually-powered application would therefore have to be specially designed and would cost more than a similar 120 volt AC generator.
- (3) The cost of the components for the low voltage DC system will be substantially increased due to the special DC generator, the lead-acid battery, battery charger, and the increased wire size necessary to carry the current at this low voltage.

2.3 Experimental Evaluation

An experimental power unit was fabricated to evaluate the concepts of manually generating electrical power with a permanent magnet generator for operation of fluorescent lamps, incandescent lamps, and other accessories.

2.3.1 Description of Experimental Unit

The experimental unit consisted of a commercially available generator mounted to a VK (Ventilation Kit) frame and transmission (see Figure 1).




Figure 1 Experimental Power Unit

GENERAL AMERICAN RESEARCH DIVISION




Figure 2 Experimental Generator Performance

GENERAL AMERICAN RESEARCH DIVISION

The generator was an eight pole, alternating current (AC), alternator with a permanent magnet rotor containing stabilized Alnico magnets and a stator wound specially for a 120 volt output (see Section 2.3.2) at 50 watts and 2000 rpm. The performance of this generator at a constant voltage output of 120 volts for various generator loads is shown in Figure 2. Since the standard generator was furnished with a pedestal mount, an adapter bracket was fabricated for mounting the generator to the frame of the VK assembly. The original VK transmission was modified to increase the speed ratio from 19.46/1 to 37.20/1 in order to obtain pedal speeds between 40 and 54 rpm at corresponding power outputs of 0 and 50 watts.

2.3.2 Lighting

The preheat fluorescent lamps from 4 through 40 watts and the 30 watt rapid-start lamp were operated individually without standard ballasts by using the experimental power unit as the power source and as the circuit ballast (see Figure 3).




Figure 3 Experimental Power Circuit, 1 Lamp

A momentary contact-type manual switch was used to start the lamps. With the switch closed, a heating current passes through the cathodes at each end of

the lamp, heating them, and causing electrons to be ejected from the cathode by thermionic emission. Upon opening the switch, a transient voltage provided by the armature windings of the generator is impressed across the cathodes of the lamp causing an electric discharge through the tube to start the lamp. The lamps were also started with either the thermal-switch or the glow-switch automatic starters. The glow-switch starter is preferred for the lighting kit, since this starter consumes no power, while the thermal-switch starter consumes 1/2 to 1-1/2 watts during lamp operation. The voltages required to sustain operation of the lamps are indicated in Table I.

Pairs of 4, 6, 8, 14, 20 and 25 watt preheat lamps were operated in series utilizing the glow-switch automatic starters (see Figure 4). With this circuit, the terminal voltage of the generator is the summation of the individual lamp operating voltages; for example, in the case of the 20-watt lamps, the terminal voltage would be 110 volts.




Figure 4 Experimental Power Circuit, 2 Lamps in Series

Pairs of 13, 30, and 40-watt preheat lamps could not be operated in series, since the necessary operating voltages are approximately 200 volts. This voltage is beyond the capability of the experimental power unit. In addition, the 30-watt rapid-start lamps could not be operated for the same reason. This lamp requires an operating voltage greater than 150 volts.

Since the generator output voltage is the summation of the individual lamp voltages when operating fluorescent lamps in series, two 20-watt lamps or two 25-watt lamps in series would require operating voltages of 110 volts and 120 volts, respectively, which are approximately the same as the voltage required for operating incandescent lamps, which can be readily operated with the experimental unit. Therefore, the recommended design voltage for the power unit is 120 volts.

2.3.3 Voltage Regulation

Fluorescent lamps that were operated with the experimental unit at power inputs less than their rated values showed a distinct "flicker". It is possible to operate a lamp at a point at which the flicker just becomes apparent. This provides the operator with a visual indication of the pedal speed necessary to keep the lamp operating. A simpler and more direct method, however, is the use of a voltmeter to maintain the correct output voltage. A voltmeter calibrated between 0 and 150 volts AC was, therefore, attached to the experimental power unit to provide a direct readout to the operator of the generator terminal voltage. This method of voltage control allows the operator to readily change pedal speed to compensate for fluctuations in output voltage due to changing loads. Therefore, a voltmeter is recommended for the power unit of the lighting kit. The significance of the voltmeter is increased if an optional incandescent lighting system is included in the kit.

GENERAL AMERICAN RESEARCH DIVISION

SECTION 3

DESIGN

The basic lighting kit includes a power unit and a fluorescent lighting system. An incandescent lighting system is proposed as an optional accessory which may be used to provide night lighting or background illumination in multi-room shelters. The output voltage of the power unit is 120 volts AC which is the standard household current, thus permitting operation of not only fluorescent and incandescent lighting systems, but also equipment such as radio receivers and dry-cell battery chargers which may be included in future shelter supplies.

3.1 Basic Lighting Kit

3.1.1 Power Unit

Two power unit designs are recommended for further development to establish which unit should be used in the shelter lighting kit. The development of both designs is necessary to determine their overall efficiency and performance, and to finalize their costs. One unit utilizes a roller chain and sprocket transmission while the other has a generator with an integral geared transmission. Both units were designed for one-man operation at a nominal power input of 0.10 horsepower at a pedal speed of 55 rpm. These human factors data were established during the development of the shelter ventilation kit (Ref. 14).

3.1.1.1 Roller Chain Transmission Design

The power unit with an external roller chain transmission is shown in Figure 5. This design is basically a unitized version of the shelter ventilator design. The main structural member is the horizontal "spine". This beam member is fabricated from 2 inch by 3 inch rectangular steel tubing. The saddle mast and mast support are welded to the spine to provide the same saddle-to-pedal angle and dimensions as those of a standard bicycle. The rear stand consists

GENERAL AMERICAN RESEARCH DIVISION




Figure 5 Power Unit With an External Roller Chain Transmission

of a steel channel shaped in an "A" frame and attached to the spine by a removable pin. The stand is designed for removal to reduce the overall dimensions for packaging purposes. The handlebar housing provides the forward support for the frame. The handlebar slides inside this housing and can be removed for packaging purposes. Height adjustment is provided by a thumbscrew. The actual height of the saddle can be adjusted by loosening the mast clamp and moving the saddle post to the desired position.

The generator is an eight pole alternating current machine with a wound stator and a permanent magnet rotor. The generator is rated at 120 volts AC and 50 watts at a nominal speed of 2000 rpm. The stator housing is flanged for mounting to the support bracket at the end of the spine. The rotor of the generator is supported by two ball bearings which are sealed and lubricated for the life of the unit. The two output lead wires of the generator are connected to a duplex outlet receptacle through a 0-150 volt AC voltmeter. Both the receptacle and voltmeter are mounted on a bracket attached to the spine.

The transmission between the crank and the generator shaft requires a two-speed step-up. The roller chain used in the transmission is American Standards Association (ASA) No. 35 with a pitch of $3/8$ inch. This chain is used rather than $1/2$ inch pitch standard bicycle chain to reduce the size of the sprockets and the centerline distance between sprockets. The sprockets for the transmission are attached either directly to the crank or to an idler shaft which is welded to the spine. The crank assembly and pedals are standard bicycle parts. This crank assembly is mounted in a tubular hanger which is welded to the spine. The sprocket at the crank has 112 teeth and is coupled with a chain to a 17 tooth sprocket at the idler shaft. Welded to this 17 tooth sprocket is a 96 tooth sprocket which is coupled to the 17 tooth sprocket on the generator shaft by a

second chain. This results in a transmission speed ratio of 37.2 to 1. This design requires a package size of 37 inches by 37 inches by 18 inches. The drawings required to fabricate a preproduction unit are presented in Appendix A.


3.1.1.2 Integral Transmission Design

The power unit using a generator with an integral transmission is shown in Figure 6. This design features a collapsible tripod stand, adjustable handlebar and saddle, and the generator with attached cranks and transmission. A 2 inch by 1 inch by 1/8 inch steel channel provides the forward leg and main structural member of the tripod frame. Welded to the top of this channel is a 3/16 inch thick steel plate which contains the hinges for the rear support legs and the mast for the saddle post. Hinged steel pads are provided at the base of all three legs to distribute the downward force. The generator mounting bracket and the handlebar housing are welded to the forward leg or channel. All three legs are connected with a wire cable to limit the spread of each leg and to add rigidity to the framework.

The generator and gear transmission are contained in one housing which is provided with a pedestal mount. The generator is rated at 120 volts AC and 50 watts at a 55 rpm input to the transmission shaft. The transmission requires no lubrication after assembly and the complete unit has a storage life of at least ten years. Two standard "3-piece" bicycle cranks are attached to the transmission input shaft.

The generator lead wires are connected to the voltmeter and duplex receptacle which are both mounted on the meter bracket. The voltmeter is calibrated between 0 and 150 volts AC and the duplex receptacle provides two separate circuits for parallel operation.

GENERAL AMERICAN RESEARCH DIVISION



Part No.	Part Name	Quantity	Material	Notes
1	Motor	1	Steel	
2	Shaft	1	Steel	
3	Gear	1	Steel	
4	Bearing	2	Steel	
5	Shaft	1	Steel	
6	Gear	1	Steel	
7	Bearing	2	Steel	
8	Shaft	1	Steel	
9	Gear	1	Steel	
10	Bearing	2	Steel	
11	Shaft	1	Steel	
12	Gear	1	Steel	
13	Bearing	2	Steel	
14	Shaft	1	Steel	
15	Gear	1	Steel	
16	Bearing	2	Steel	
17	Shaft	1	Steel	
18	Gear	1	Steel	
19	Bearing	2	Steel	
20	Shaft	1	Steel	

Figure 4. Power Unit With an Integral Geared Transmission

GENERAL AMERICAN RESEARCH DIVISION

This design requires a package size 45 inches by 18 inches by 14 inches. The drawings required to fabricate a preproduction unit are presented in Appendix B.

3.1.2 Fluorescent Lighting System

The fluorescent lighting system consists of two preheat fluorescent lamps and two lamp fixtures. The rating of the lamps to be furnished with the kit is subject to verification of the transmission efficiency of the selected power unit. It is expected that two 20-watt lamps would be furnished for the power unit with a roller chain and sprocket transmission, and two 25-watt lamps for the power unit, which has a generator with an integral geared transmission.

Two adjustable fixtures with cords are furnished with each kit. The fixtures, shown in Figure 7, can be adjusted to accept 15 through 40 watt lamps, which range in length from 18 to 48 inches. Each fixture contains an automatic starter of the glow-switch type. One fixture has a female receptacle at one end, for connecting the second fixture in series, and a 20-foot long cord with a molded male plug at the other end. This fixture is only used when operating two fluorescent lamps in series. The second fixture has a 100-foot electrical cord with a molded male plug. This fixture has no female receptacle and is used either singly or in series (see Figure 8). The fixture is designed to accommodate a 40-watt lamp, since in most cases, this size lamp is more likely to be found in the shelters if the stocked lamps are broken. The lengths of the cords attached to each fixture should be verified by additional analysis of shelter sizes and configurations (Ref. 15). Both electrical cords are 2-wire, 18 gage, SPT type which is the minimum wire gage suitable for these lengths and connections. The fixture with the 20-foot cord is intended for use at the ceiling of the room in which the power unit is located. The other fixture with the 100-foot

GENERAL AMERICAN RESEARCH DIVISION




Figure 7 Adjustable Fluorescent Fixture

cord is intended for use in an adjacent room in the shelter.




Figure 8 Fluorescent Lighting System

3.1.3 Cost Analysis

The cost of the basic lighting kit using a power unit with a roller chain transmission is \$90, based on a production of 100,000 units (see Table V). The cost of a lighting kit with a power unit having a generator with an integral geared transmission ranges from \$88 to \$111 (see Table VI). This variation is due to the estimated production cost of the generator with an integral geared transmission. Based on firm quotations from manufacturers (Refs. 16 and 17), this cost is between \$30 and \$50 depending on whether economical production techniques such as powdered-metal gears, nylon gears, sleeve bearings, etc. can be used. A closer estimate is not possible at this time without a complete engineering design and production cost evaluation by the generator manufacturers.

3.2 Accessory Incandescent Lighting System

An analysis of shelter sizes, configurations, and human factors should be conducted to determine if an incandescent lighting system is warranted as an accessory of the lighting kit, since this type of lighting might be used advantageously in multi-room shelters as background illumination. This type of lighting can also be used to supply low level night illumination for sleeping at a very minimum cost. The incandescent lighting system is therefore proposed as an optional accessory. and, if adopted, would consist of the following items in addition to the fluorescent lighting system (see Figure 9):

- (1) Five (5) extension cords, type SPT, 2-wire, 18 gage, with molded male

TABLE V

Cost Analysis of Lighting Kit Using a Power Unit WithA Roller Chain Transmission

Purchased Parts & Material: \$ 46.68

<u>Drawing No. & Item</u>	<u>Description</u>	<u>Cost</u>
1400-1 00A Item 1	Saddle	\$0.87
Item 2	Clamp, Saddle Post	0.09
Item 3	Bolt	0.04
Item 4	Nut	0.02
Item 11	Thumbscrew	0.022
Item 12	Chain, 130 Pitches	2.25
Item 14	Retaining Ring	0.005
Item 15	Chain, 111 Pitches	1.92
Item 16	Screw	0.02
Item 17	Sprocket	0.42
Item 18	Screws	0.04
Item 19	Washers	0.02
Item 20	Generator	30.00
Item 21	Bearing Cup	0.22
Item 22	Bearing	0.094
Item 23	Cone, Locking	0.128
Item 24	Crank	1.40
Item 25	Pedals	0.46
Item 26	Cone, Adjusting	0.128
Item 27	Washer	0.011
Item 28	Locknut	0.048
Item 30	Receptacle	0.38
Item 31	Voltmeter	1.44
1400-1001A	Nut, Weld	0.034
1400-1005A	Sprocket	2.91
1400-1007A	Sprocket	3.14
1400-1001A (material)	Frame	2.65
1400-1002A (material)	Pin, Locating	0.22
1400-1003A (material)	Stand	0.49
1400-1004A (material)	Post, Saddle	0.29
1400-1006A (material)	Handlebar	0.82
1400-1008A (material)	Bracket, Meter	0.14
	Lamp Fixtures (2)	1.80
	Lamps, Fluorescent (2)	1.32
	Starters (2)	0.24
	Wiring Loom, 20 Feet	0.65
	Wiring Loom, 100 Feet	2.25

Packaging: \$ 9.00

Inner Box, Triple-Wall (PPP-B-640)	3.80
Bag, Barrier (MLL-B-131, Class 1)	3.21
Exterior Container (PPP-B-636)	1.83

Finishing: \$ 5.70

1400-1005A	Sprocket	0.40
1400-1007A	Sprocket	0.40
1400-1001A	Frame	3.50
1400-1002A	Pin, Locating	0.05
1400-1003A	Stand	0.60
1400-1004A	Post, Saddle	0.20
1400-1006A	Handlebar	0.50
1400-1008A	Bracket, Meter	0.05

Labor: \$ 8.12

Arc Welding	5.75
Machining & Assembly	2.37

Labor Overhead: (100%): \$ 8.12

Sub-Total	77.62
General & Administrative Services: (8%).	6.21

Sub-Total	83.83
---------------------	-------

Profit: (7%) 5.87

TOTAL \$89.70

- NOTES: 1) Based on 100,000 units.
2) No freight costs included.

TABLE VI

Cost Analysis of Lighting Kit Using a Power Unit With
A Generator Having an Integral Geared Transmission

Purchased Parts & Material: \$46.23 - \$66.23

<u>Drawing No. & Item</u>	<u>Description</u>	<u>Cost</u>
1400-1000B Item 1	Saddle	\$0.87
Item 3	Clamp, Saddle Post	0.09
Item 4	Nut	0.02
Item 5	Bolt	0.04
Item 8	Wire Cable	0.27
Item 9	Sleeve, Splicing	0.12
Item 11	Pin, Clevis	0.24
Item 13	Thumbscrew	0.022
Item 14	Voltmeter	1.44
Item 15	Receptacle	0.38
Item 17	Bolt	0.08
Item 18	Nut	0.04
Item 19	Washer	0.005
Item 20	Generator	30.00-50.00
Item 21	Bolt, Eye	0.043
Item 22	Washer	0.002
Item 23	Nut	0.004
Item 24	Pin, Clevis	0.06
Item 26	Crank, Right	1.20
Item 27	Pedals	0.46
Item 28	Crank, Left	1.20
Item 29	Pin, Nut, Washer set	0.10
1400-1002B	Nut, Weld	0.034
1400-1001B (material)	Post, Saddle	0.19
1400-1002B (material)	Frame	1.21
1400-1003B (material)	Leg	0.88
1400-1004B (material)	Foot, Rear	0.22
1400-1005B (material)	Handlebar	0.82
1400-1006B (material)	Bracket, Meter	0.12
1400-1007B (material)	Foot, Front	0.11
	Lamp Fixtures (2)	1.80
	Lamps, Fluorescent (2)	1.02
	Starters, (2)	0.24
	Wiring Loom, 20 Feet	0.65
	Wiring Loom, 100 Feet	2.25
<u>Packaging:</u>		4.76
	Inner Box, Triple-Wall (PPP-B-640)	2.09
	Bag, Barrier (MLL-B-131, Class 1)	1.72
	Exterior Container (PPP-B-636)	0.95
<u>Finishing:</u>		5.75
1400-1001B	Post, Saddle	0.35
1400-1002B	Frame	3.50
1400-1003B	Leg	0.80
1400-1004B	Foot, Rear	0.30
1400-1005B	Handlebar	0.50
1400-1006B	Bracket, Meter	0.10
1400-1007B	Foot, Front	0.20
<u>Labor:</u>		9.67
	Arc Welding	7.80
	Machining & Assembly	1.87
<u>Labor Overhead: (100%)</u>		9.67
Sub-Total.		76.08 - 96.08
<u>General & Administrative Services: (8%)</u>		6.09 - 7.69
Sub-Total.		82.17 - 103.77
<u>Profit: (7%)</u>		5.75 - 7.26
TOTAL		\$87.92 - \$111.03

NOTES: 1) Based on 100,000 units.
 2) No freight costs included.




Figure 9 Incandescent Lighting System

GENERAL AMERICAN RESEARCH DIVISION

plug, 115 volt, 15 ampere at one end, and a cube tap, molded, 125 volt, 15 ampere at the other end. The length of the cords is subject to an analysis of shelter sizes and configurations (Ref. 15).

(2) Five (5) bakelite adaptor sockets, 660 watt, 125 volt, medium base.

(3) Five (5) 10-watt incandescent lamps.

The electrical ratings for the cords and adaptors are minimum for the possible lengths of wire and connections as shown in Figure 9.

The estimated cost of this system is \$7.30 based on original equipment manufacturer's cost for 100,000 units of the following items.

<u>Item</u>	<u>Quantity Required</u>	<u>Total Cost</u>
Extension Cord, 50 feet	5	\$ 6.25
Adapter Socket	5	0.50
Incandescent Lamp, 10-watt	5	<u>0.55</u>
	Total	\$ 7.30

REFERENCES

1. Smith, M. C. and Wendel, W. J., "Illumination In Group Shelters", Part I, prepared for the Office of Civil Defense under Contract OCD-OS-62-80, Sanders and Thomas, Inc., Pottstown, Pa., January 1963, p. 33.
2. Ibid, Part II, March 1963.
3. Fabuss, B. M. and Barsanyi, A. S., "Self-Contained Generator for Shelter Use", prepared for the Office of Civil Defense under Contract OCD-PS-64-7, Monsanto Research Corporation, Boston Laboratory, Everett, Massachusetts, October 1964.
4. Lauck, F. W., et. al., "Small Auxiliary Power Systems", prepared for the Office of Civil Defense, under Contract OCD-OS-62-282, A. O. Smith Corp., Long Range Research Laboratory, Milwaukee, Wisconsin, May 1964.
5. "Improvised Power Supplies", prepared for the Office of Civil Defense under Contract OCD-OS-62-281, The General Electric Company, Military Communications Department, Nuclear Effects Product Engineering, Syracuse, New York, June 1964.
6. Libovicz, B. A. and Behls, H. F., "Shelter Package Ventilation Kit", prepared for the Office of Civil Defense under Work Unit 1423A, Contract OCD-PS-64-22, General American Transportation Corporation, (GARD Report 1244), Niles, Illinois, October 1965.
7. Illuminating Engineering Society, "IES Lighting Handbook", Third Edition, 1959, New York, Section 8.
8. Neveril, R. B., Private Communication with P. Finstad, General Electric Company, December 1966.
9. Op. Cit., "IES Lighting Handbook".
10. General Electric Form 2195, "Large Lamp Price Schedule", Effective November 1, 1965.
11. Neveril, R. B., Private Communication with A. Hook, General Electric Company, December 1966.
12. Op. Cit., "Improvised Power Supplies", pp. 9-12.
13. Op. Cit., Libovicz, B. A., GARD Report 1244, p. 60.

REFERENCES (CONT'D)

14. Libovicz, B. A. and Behls, H. F., "Experimental Prototype Package Ventilation Kit, First Structural and Human Factors Test", prepared for the Office of Civil Defense under Stanford Research Institute Sub-contract No. B-70925(4949A-28)-US, General American Transportation Corporation (GARD Report 1278-4.1), Niles, Illinois, May 1965, p.4.
15. Hill, E. L., et. al., "Determination of Shelter Configuration for Ventilation", prepared for the Office of Civil Defense under Work Unit 1235A, Contract OCD-PS-64-56, Research Triangle Institute (RTI Report R-OU-177), Durham, N. C., July 1965.
16. Globe Industries, Inc., Dayton, Ohio, Quotation dated August 31, 1966.
17. Varo, Inc., Santa Barbara, California, Quotation No. 076-387, dated October 4, 1966.


GENERAL AMERICAN RESEARCH DIVISION

APPENDIX A


--DRAWINGS--

POWER UNIT WITH AN EXTERNAL ROLLER CHAIN
TRANSMISSION


GENERAL AMERICAN RESEARCH DIVISION




GENERAL AMERICAN RESEARCH DIVISION



GENERAL AMERICAN RESEARCH DIVISION





GENERAL AMERICAN RESEARCH DIVISION

A 1400-1001A-8		REV 500		CHANGE		JUNE 67		DATE	
----------------	--	---------	--	--------	--	---------	--	------	--

MATERIAL:
 2.250 ±.006 O.D. x 12 B.W. GA. (.109 +.002, -.008) WALL
 ELECTRIC WELDED HOT ROLLED STEEL TUBING. C1010. PICKLED.
 WELD FLASH CONTROLLED TO .010 MAX.

NO NEW SCALE DRAWING		SCALE FULL		DATE 12/5/66		DRAWN JAA		CHECKED RBN		APPROVED JTB	
1400-1001A		NEXT ASSEMBLY		12/6/66		12/5/66		12/5/66		12/5/66	

GENERAL AMERICAN TRANSPORTATION CORPORATION				MATERIAL SPEC. SEE NOTE				MAT. SIZE OR PATTERN NO.			
PART NAME HANGER, CRANK				CLASS				DIV.			
DWO. A				SIZE				NUMBER 1400-1001A-8			
TIME				MODEL							

A 1400-1001A-9		ENG. CHANGE NO.	REV. SUB	CHANGE	ZONE	BY	DATE
----------------	--	-----------------	----------	--------	------	----	------

3.500

32

.4983
.4978

.03 x 45° CHAMFER

.470
.466

0.004
0.0041

0.005 R. MAX.

DETAIL SCALE: 5:1

ITEM		SIZE	PART NO.	REQ'D	DESCRIPTION	
GENERAL AMERICAN TRANSPORTATION CORPORATION						
MATERIAL SPEC.		C.D.S. C1018				
MAT. SIZE OR PATTERN NO.						
CLASS		DIV.		DWG.	NUMBER	MODEL
SHAFT				A	1400-1001A-9	

DO NOT SCALE DIMENSIONS		DATE	
SCALE FULL	AS NOTED	12/6/66	
DRAWN		JAB	
CHECKED	RBN	12/6/66	
APPROVED	JAB	12/6/66	

1400-1001A	1400-1001A
1400-1001A	1400-1001A

GENERAL AMERICAN RESEARCH DIVISION

A 1400-1002A		NAME		ZONE BY DATE	
ENL. CHANGE NO. REV 300					

$\frac{1}{32} \times 45^\circ$ CHAMFER

.156 DIA. HOLE

5 $\frac{3}{4}$

.22

2

.375 DIA.

$\frac{1}{8}$ DIA.

FINISH: MANGANESE PHOSPHATE COAT
PER 5.3.1.3 OF MIL-STD-171; & DRY FILM
LUBRICANT PER MIL-L-8937.

2	AEROFAST R-1.00 OR EQ.	1	RING, HANDLE, 1" DIA. NOM.; CAD. PLATE.
1	1400-1002A	1	PIN


ITEM	SIZE	PART NO.	REQ'D	DESCRIPTION
GENERAL AMERICAN TRANSPORTATION CORPORATION				
MATERIAL SPEC. STEEL, C1144 OR EQUAL		MAT. SIZE OR PATTERN NO.		
CLASS		DIV.	DWG.	NUMBER
1400-1000A			A	1400-1002A
NEXT ASSEMBLY		MODEL		


NO NET SCALE DRAWING		DATE	
SCALE	FULL	12/12/66	
DRAWN	JAA	12/12/66	
CHECKED	BBM	12/12/66	
APPROVED	JTB	12/12/66	

PART NAME
PIN, LOCATING

STANDARD LIMITS UNLESS OTHERWISE SPECIFIED ARE


FORM 4000






1400	A	1007A-2	EVL. CHANGE NO.	REV	SUB	NAME	ZONE	BY	DATE
------	----------	---------	-----------------	-----	-----	------	------	----	------

17 TEETH A.S.A. 35
PITCH 2.04 PD




BOTTOM DIA.
⊙ A .006 TIR




HEAT TREATMENT: CARBURIZE APPROX.
.015 DEEP, INDUCTION HARDEN TEETH
ONLY, AND TEMPER TO ROCKWELL C40-45

IS NOT SCALE DRAWING		SCALE		DATE	
1400-1007A	1400-1007A	FULL	12/1/66		
NEXT ASSEMBLY	APPROVED	DRAWN	CHECKED		

GENERAL AMERICAN TRANSPORTATION CORPORATION			
MATERIAL SPEC. B1113 STEEL	MAT. SIZE OR PATTERN NO.	DWG. NO.	NUMBER
		A	1400-1007A-2




1400	A	1001A-3	END. CHANGE NO.	REV. NO.	CHANGE	ZONE	BY	DATE
------	---	---------	-----------------	----------	--------	------	----	------



MATERIAL: SINTERED BRONZE, OIL IMPREGNATED, PER MIL-B-5687A, TYPE-1, COMP.A.

ITEM		SIZE	PART NO.	REQ'D	DESCRIPTION	
			GENERAL AMERICAN TRANSPORTATION CORPORATION			
MATERIAL SPEC.		MATERIAL SPEC. OR PATTERN NO.				
AS NOTED						
PART NAME		CLASS	DIV.	DWG. NUMBER	MODEL	
BEARING SLEEVE, SPROCKET				A 1400-1007A-3		
1400-1001A		SCALE	DATE			
NEXT ASSEMBLY		DRAWN	DATE			
		CHECKED	DATE			
		APPROVED	DATE			





APPENDIX B

--DRAWINGS--

POWER UNIT WITH AN INTEGRAL GEARED TRANSMISSION


GENERAL AMERICAN RESEARCH DIVISION






GENERAL AMERICAN RESEARCH DIVISION

DATE	11/1/66	BY	JJA
SCALE	1/4" = 1'	PROJECT NO.	1400 - 10000 B
DESCRIPTION	WIRE MESH STRUCTURE		
DESIGNED BY	JJA		
CHECKED BY	JJA		
APPROVED BY	JJA		
REVISIONS	2-2		




MATERIAL: .875x.004 O.D. x .16 DIA GA (.065) MWL ELECTRIC WELDED
COLD ROLLED STEEL TUBING. C1010.
FINISH: MANGANESE PHOSPHATE COAT PER 5.3-1.3 OF
MIL-STD-171, AND DRY FILM LUBRICANT PER MIL-L-8937.

ITEM	QTY	DATE	BY	REVISION	DESCRIPTION
1	1	12-1-54	WJG	1	POST, SADDLE
2	1	12-1-54	WJG	2	AS NOTED
3	1	12-1-54	WJG	3	AS NOTED
4	1	12-1-54	WJG	4	AS NOTED
5	1	12-1-54	WJG	5	AS NOTED
6	1	12-1-54	WJG	6	AS NOTED
7	1	12-1-54	WJG	7	AS NOTED
8	1	12-1-54	WJG	8	AS NOTED
9	1	12-1-54	WJG	9	AS NOTED
10	1	12-1-54	WJG	10	AS NOTED
11	1	12-1-54	WJG	11	AS NOTED
12	1	12-1-54	WJG	12	AS NOTED
13	1	12-1-54	WJG	13	AS NOTED
14	1	12-1-54	WJG	14	AS NOTED
15	1	12-1-54	WJG	15	AS NOTED
16	1	12-1-54	WJG	16	AS NOTED
17	1	12-1-54	WJG	17	AS NOTED
18	1	12-1-54	WJG	18	AS NOTED
19	1	12-1-54	WJG	19	AS NOTED
20	1	12-1-54	WJG	20	AS NOTED
21	1	12-1-54	WJG	21	AS NOTED
22	1	12-1-54	WJG	22	AS NOTED
23	1	12-1-54	WJG	23	AS NOTED
24	1	12-1-54	WJG	24	AS NOTED
25	1	12-1-54	WJG	25	AS NOTED
26	1	12-1-54	WJG	26	AS NOTED
27	1	12-1-54	WJG	27	AS NOTED
28	1	12-1-54	WJG	28	AS NOTED
29	1	12-1-54	WJG	29	AS NOTED
30	1	12-1-54	WJG	30	AS NOTED
31	1	12-1-54	WJG	31	AS NOTED
32	1	12-1-54	WJG	32	AS NOTED
33	1	12-1-54	WJG	33	AS NOTED
34	1	12-1-54	WJG	34	AS NOTED
35	1	12-1-54	WJG	35	AS NOTED
36	1	12-1-54	WJG	36	AS NOTED
37	1	12-1-54	WJG	37	AS NOTED
38	1	12-1-54	WJG	38	AS NOTED
39	1	12-1-54	WJG	39	AS NOTED
40	1	12-1-54	WJG	40	AS NOTED
41	1	12-1-54	WJG	41	AS NOTED
42	1	12-1-54	WJG	42	AS NOTED
43	1	12-1-54	WJG	43	AS NOTED
44	1	12-1-54	WJG	44	AS NOTED
45	1	12-1-54	WJG	45	AS NOTED
46	1	12-1-54	WJG	46	AS NOTED
47	1	12-1-54	WJG	47	AS NOTED
48	1	12-1-54	WJG	48	AS NOTED
49	1	12-1-54	WJG	49	AS NOTED
50	1	12-1-54	WJG	50	AS NOTED
51	1	12-1-54	WJG	51	AS NOTED
52	1	12-1-54	WJG	52	AS NOTED
53	1	12-1-54	WJG	53	AS NOTED
54	1	12-1-54	WJG	54	AS NOTED
55	1	12-1-54	WJG	55	AS NOTED
56	1	12-1-54	WJG	56	AS NOTED
57	1	12-1-54	WJG	57	AS NOTED
58	1	12-1-54	WJG	58	AS NOTED
59	1	12-1-54	WJG	59	AS NOTED
60	1	12-1-54	WJG	60	AS NOTED
61	1	12-1-54	WJG	61	AS NOTED
62	1	12-1-54	WJG	62	AS NOTED
63	1	12-1-54	WJG	63	AS NOTED
64	1	12-1-54	WJG	64	AS NOTED
65	1	12-1-54	WJG	65	AS NOTED
66	1	12-1-54	WJG	66	AS NOTED
67	1	12-1-54	WJG	67	AS NOTED
68	1	12-1-54	WJG	68	AS NOTED
69	1	12-1-54	WJG	69	AS NOTED
70	1	12-1-54	WJG	70	AS NOTED
71	1	12-1-54	WJG	71	AS NOTED
72	1	12-1-54	WJG	72	AS NOTED
73	1	12-1-54	WJG	73	AS NOTED
74	1	12-1-54	WJG	74	AS NOTED
75	1	12-1-54	WJG	75	AS NOTED
76	1	12-1-54	WJG	76	AS NOTED
77	1	12-1-54	WJG	77	AS NOTED
78	1	12-1-54	WJG	78	AS NOTED
79	1	12-1-54	WJG	79	AS NOTED
80	1	12-1-54	WJG	80	AS NOTED
81	1	12-1-54	WJG	81	AS NOTED
82	1	12-1-54	WJG	82	AS NOTED
83	1	12-1-54	WJG	83	AS NOTED
84	1	12-1-54	WJG	84	AS NOTED
85	1	12-1-54	WJG	85	AS NOTED
86	1	12-1-54	WJG	86	AS NOTED
87	1	12-1-54	WJG	87	AS NOTED
88	1	12-1-54	WJG	88	AS NOTED
89	1	12-1-54	WJG	89	AS NOTED
90	1	12-1-54	WJG	90	AS NOTED
91	1	12-1-54	WJG	91	AS NOTED
92	1	12-1-54	WJG	92	AS NOTED
93	1	12-1-54	WJG	93	AS NOTED
94	1	12-1-54	WJG	94	AS NOTED
95	1	12-1-54	WJG	95	AS NOTED
96	1	12-1-54	WJG	96	AS NOTED
97	1	12-1-54	WJG	97	AS NOTED
98	1	12-1-54	WJG	98	AS NOTED
99	1	12-1-54	WJG	99	AS NOTED
100	1	12-1-54	WJG	100	AS NOTED



GENERAL AMERICAN RESEARCH DIVISION

A 1400-1002B-3		REV SUB		NAME		ZONE BY DATE	
----------------	--	---------	--	------	--	--------------	--



MATERIAL: 3/4 x 3/4 x 1/8 ANGLE
BAR SIZE: M1020

ITEM SIZE		PART NO.		REQ'D		DESCRIPTION	
						GENERAL AMERICAN TRANSPORTATION CORPORATION	
		MATERIAL SPEC.		MAT. SIZE OR PATTERN NO.		AS NOTED	
		CLASS		DIV.		NUMBER	
		—		—		A 1400-1002B-3	
		PART NAME		HINGE		MODEL	
		IS IN FILE NUMBER					
SCALE		DATE					
DRAWN		11/6/66					
CHECKED		JAA					
APPROVED		7/26/66					
1400-1002B							
NEXT ASSEMBLY							

ITEM		SIZE	PART NO.	REVISED	DESCRIPTION	
			GENERAL AMERICAN TRANSPORTATION CORPORATION			
			MATERIAL SPEC.	MAX. SIZE OR PATTERN NO.		
			AS NOTED	AS NOTED		
			CLASS	DIV.	NUMBER	MODEL
			GUIDE, HANDLEBAR		1400-1002B-4	

IS IN SIZE		DATE
SCALE	FULL	12/15/66
DRAWN	ERN	
CHECKED	JAA	12/16/66
APPROVED		12/16/66

1400-1002B	1400-1002B-4
1400-1002B-4	1400-1002B-4

7.00

.62

547 DIA. HOLE THROUGH THIS WALL ONLY

MATERIAL: 1" SQUARE x 13 BVG (.095)
WALL ELECTRIC WELDED CRS TUBING,
C1010. WELD FLASH CONTROLLED
TO .010 MAX. CONVEITY AND
CONCAVITY .010 MAX

GENERAL AMERICAN RESEARCH DIVISION

A	1400-1002B-5	REV SUB	NAME	DATE	BY	DATE
----------	--------------	---------	------	------	----	------

GENERAL AMERICAN TRANSPORTATION CORPORATION

MATERIAL SPEC.
HOT ROLLED STEEL
M1020

CLASS — **DIV.** — **DWG.** **A** **NUMBER** 1400-1002B-5


PART NAME
BRACKET, GENERATOR

ITEM — **SIZE** — **PART NO.** — **REQ'D** — **DESCRIPTION**


DO NOT SCALE DRAWING SCALE FULL DRAWN RBN CHECKED JAA APPROVED NEXT ASSEMBLY	DATE 11/5/66 12/6/66 12/6/66	CHECKING LIMITS UNLESS OTHERWISE SPECIFIED 	PART NAME BRACKET, GENERATOR	CLASS — DIV. — DWG. A NUMBER 1400-1002B-5	MATERIAL SPEC. HOT ROLLED STEEL M1020	GENERAL AMERICAN TRANSPORTATION CORPORATION
--	------------------------------------	--	--	--	---	---

FORM 4100A


GENERAL AMERICAN RESEARCH DIVISION



GENERAL AMERICAN RESEARCH DIVISION



GENERAL AMERICAN RESEARCH DIVISION





MATERIAL: $\frac{3}{4}$ O.D. = 1.315 IN. (O.D.) WALL
ELECTRIC WELDED HOT ROLLED STEEL
TUBING. PICKLED. C/OVO.



**CROSSBAR,
HANDLEBAR**


FINISH:
 MANGANESE PHOSPHATE COAT PER 3.8.15
 OR MIL-STD-171, V. III
 OR MIL-STD-171, 4 WHITE FINISH COAT No 27875
 OR FED-STD-598, POLYURETHANE PER
 MIL-C-27227

MATERIAL
 TO Q. (2000) C1020 CRS.



1400 C 1400-1000B

DATE	BY	CHKD	APP'D	REV	QTY	UNIT	REMARKS
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	
10/1/50	JAA	JAA	JAA	1	1	BRACKET, METER	



UNCLASSIFIED

Security Classification

DOCUMENT CONTROL DATA - R&D		
(Security classification of title, body of abstract and indexing annotation must be entered when the overall report is classified)		
1. ORIGINATING ACTIVITY (Corporate author) General American Transportation Corporation 7449 N. Natchez Avenue Niles, Illinois 60648		2a. REPORT SECURITY CLASSIFICATION Unclassified
		2b. GROUP
3. REPORT TITLE SHELTER LIGHTING KIT (J)		
4. DESCRIPTIVE NOTES (Type of report and inclusive dates) Final Report		
5. AUTHOR(S) (Last name, first name, initial) Neveril, Robert B. Behls, Herman F.		
6. REPORT DATE January, 1967	7a. TOTAL NO. OF PAGES 86	7b. NO. OF REFS 17
8a. CONTRACT OR GRANT NO. SRI Subcontract No. B-8700(4949A-62)-US	9a. ORIGINATOR'S REPORT NUMBER(S) GARD Report 1400	
a. PROJECT NO. OCD Work Unit 1427A	9b. OTHER REPORT NO(S) (Any other numbers that may be assigned this report) None	
c.		
d.		
10. AVAILABILITY/LIMITATION NOTICES Distribution of this document is unlimited.		
11. SUPPLEMENTARY NOTES		12. SPONSORING MILITARY ACTIVITY Office of Civil Defense Department of the Army, OSA Washington, D. C. 20310
13. ABSTRACT <p>The Shelter Lighting Kit includes a manually-driven power unit and a fluorescent lighting system. Two power unit designs are presented for preproduction fabrication and evaluation. One power unit has a generator mounted on a bicycle-type frame and driven by a chain and sprocket transmission; while the other unit has a generator with an integral geared transmission mounted on a folding tripod frame. Both power units are designed for one-man operation with a power input of 0.1 horsepower at a nominal pedal speed of 95 rpm and a nominal generator output of 50 watts at 120 volts AC. The selection of either design for the production model will depend on their performance and a cost analysis. The fluorescent lighting system consists of two adjustable lamp fixtures and two 20-watt or 25-watt pre-heat fluorescent lamps operated in series (selected lamp wattage will depend on the overall system efficiency). The estimated production cost of the lighting kit is \$90. (u)</p> <p>An incandescent lighting system is proposed as an optional accessory for night lighting or background illumination in multi-room shelters. This lighting system consists of five 10-watt incandescent lamps with adapter sockets and five 50-foot extension cords. The estimated cost of this accessory is \$7.30. (u)</p>		

DD FORM 1 JAN 66 1473

UNCLASSIFIED
Security Classification

UNCLASSIFIED
Security Classification

14. KEY WORDS	LINK A		LINK B		LINK C	
	ROLE	WT	ROLE	WT	ROLE	WT
CIVIL DEFENSE SYSTEMS FALL-OUT SHELTERS DESIGN GENERATORS PORTABLE EXERCISE LIGHT LIGHTING EQUIPMENT BATTERIES & COMPONENTS RADIO COMMUNICATION SYSTEMS						

INSTRUCTIONS

1. ORIGINATING ACTIVITY: Enter the name and address of the contractor, subcontractor, grantee, Department of Defense activity or other organization (corporate author) issuing the report.

2a. REPORT SECURITY CLASSIFICATION: Enter the overall security classification of the report. Indicate whether "Restricted Data" is included. Marking is to be in accordance with appropriate security regulations.

2b. GROUP: Automatic downgrading is specified in DoD Directive 5200.10 and Armed Forces Industrial Manual. Enter the group number. Also, when applicable, show that optional markings have been used for Group 3 and Group 4 as authorized.

3. REPORT TITLE: Enter the complete report title in all capital letters. Titles in all cases should be unclassified. If a meaningful title cannot be selected without classification, show title classification in all capitals in parenthesis immediately following the title.

4. DESCRIPTIVE NOTES: If appropriate, enter the type of report, e.g., interim, progress, summary, annual, or final. Give the inclusive dates when a specific reporting period is covered.

5. AUTHOR(S): Enter the name(s) of author(s) as shown on or in the report. Enter last name, first name, middle initial. If military, show rank and branch of service. The name of the principal author is an absolute minimum requirement.

6. REPORT DATE: Enter the date of the report as day, month, year, or month, year. If more than one date appears on the report, use date of publication.

7a. TOTAL NUMBER OF PAGES: The total page count should follow normal pagination procedures, i.e., enter the number of pages containing information.

7b. NUMBER OF REFERENCES: Enter the total number of references cited in the report.

8a. CONTRACT OR GRANT NUMBER: If appropriate, enter the applicable number of the contract or grant under which the report was written.

8b, 8c, & 8d. PROJECT NUMBER: Enter the appropriate military department identification, such as project number, subproject number, system numbers, task number, etc.

9a. ORIGINATOR'S REPORT NUMBER(S): Enter the official report number by which the document will be identified and controlled by the originating activity. This number must be unique to this report.

9b. OTHER REPORT NUMBER(S): If the report has been assigned any other report numbers (either by the originator or by the sponsor), also enter this number(s).

10. AVAILABILITY/LIMITATION NOTICES: Enter any limitations on further dissemination of the report, other than those imposed by security classification, using standard statements such as:

- (1) "Qualified requesters may obtain copies of this report from DDC."
- (2) "Foreign announcement and dissemination of this report by DDC is not authorized."
- (3) "U. S. Government agencies may obtain copies of this report directly from DDC. Other qualified DDC users shall request through _____."
- (4) "U. S. military agencies may obtain copies of this report directly from DDC. Other qualified users shall request through _____."
- (5) "All distribution of this report is controlled. Qualified DDC users shall request through _____."

If the report has been furnished to the Office of Technical Services, Department of Commerce, for sale to the public, indicate this fact and enter the price, if known.

11. SUPPLEMENTARY NOTES: Use for additional explanatory notes.

12. SPONSORING MILITARY ACTIVITY: Enter the name of the departmental project office or laboratory sponsoring (paying for) the research and development. Include address.

13. ABSTRACT: Enter an abstract giving a brief and factual summary of the document indicative of the report, even though it may also appear elsewhere in the body of the technical report. If additional space is required, a continuation sheet shall be attached.

It is highly desirable that the abstract of classified reports be unclassified. Each paragraph of the abstract shall end with an indication of the military security classification of the information in the paragraph, represented as (TS), (S), (C), or (U).

There is no limitation on the length of the abstract. However, the suggested length is from 150 to 225 words.

14. KEY WORDS: Key words are technically meaningful terms or short phrases that characterize a report and may be used as index entries for cataloging the report. Key words must be selected so that no security classification is required. Identifiers, such as equipment model designation, trade name, military project code name, geographic location, may be used as key words but will be followed by an indication of technical context. The assignment of links, rules, and weights is optional.

UNCLASSIFIED
Security Classification